



BILL TO
CITY OF VERGAS
PO BOX 32
VERGAS, MN 56587 USA

ESTIMATE 42738526

Oct 27, 2023

JOB ADDRESS NEW OFFICE 131 E. MAIN ST 131 East Main Street Vergas, MN 56587 USA Job:

TASK DESCRIPTION

QTY PRICE

\$8,851.00

1.00

TOTAL

\$8,851.00

**BIDHVACR** 

INSTALL A NEW BRYANT PREFERRED 2 TON UP TO 23 SEER MULTIZONE DUCTLESS HEAT PUMP SYSTEM INTO THE NEW OFFICE BUILDING. REMOVE AND DISPOSE OF THE OLD LG DUCTLESS AIR CONDITIONER. PLACE THE NEW 2 TON OUTDOOR CONDENSER 38MGRBQ24CA3 ON A HEAT PUMP STAND AND 2" THICK PLASTIC PAD IN PLACE OF THE OLD CONDENSER. RUN THE FIRST 1/4"X3/8" LINESET STRAIGHT UP AND INTO THE EXISTING HOLE TO THE FIRST OFFICE 1/2 TON 6,000BTU INDOOR HIGH WALL AIR HANDLER 619AHBQ06XA3. RUN THE CONDENSATION DRAIN BACK OUT AND COVER THE LINES WITH LINEHIDE. RUN THE SECOND 1/4"X1/2" LINESET OVER AND THRU THE STORAGE CLOSET OF OFFICE NUMBER 1 INTO THE MAIN MEETING AREA TO A 1 TON 12,000BTU INDOOR HIGH WALL AIR HANDLER 619AHBQ12XA3. RUN THE CONDENSATION DRAIN BACK OUT AND COVER BOTH LINES OUTSIDE WITH LINEHIDE. RUN THE 3RD 1/4"X3/8" LINESET INSIDE THRU OFFICE 1 STORAGE CLOSET AND THRU THE MEETING ROOM BUILT IN CABINETS LOW TO THE 2ND OFFICE AND UP TO A 1/2 TON 6,000BTU INDOOR HIGH WALL AIR HANDLER. GRAVITY DRAIN THE CONDENSATION DRAIN BACK OUT AND COVER BOTH LINES OUTSIDE WITH LINEHIDE. EACH INDOOR AIR HANDLER COMES WITH A WIRELESS REMOTE CONTROL.

1 YEAR COMMERCIAL WARRANTY AND 1 YEAR LABOR WARRANTY. ELECTRICAL NOT INCLUDED IN THE BID (OUTDOOR CONDENSER NEEDS 220V MAX AMPS OF 35)

ELECTRIC PROVIDER REBATES MAY BE AVAILABLE DEPENDING ON THE PROVIDER.

TOTAL INSTALLED: \$8,851

-

Estimate #42738526 Page 1 of 2

POTENTIAL SAVINGS

\$0.00

SUB-TOTAL

\$8,851.00

TOTAL

\$8,851.00

Thank you for placing your trust in our company! If you have any questions or concerns please feel free to reach out to us.

All returned material may be subject to a 30% restocking fee. Any invoice not paid within 30 days will be subject to finance charges of 1.5% monthly/18% annually.

## **CUSTOMER AUTHORIZATION**

All material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. Customer accepts responsibility for projects that would require Architect or Engineering license. Any alteration or deviation from above specifications involving extra costs will become an extra charge over and above the estimate. All agreements contingent upon delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workman's Compensation Insurance. Purchaser agrees to pay all costs of collection, including attorney's fees. This proposal may be withdrawn by us if not accepted within 30 days of the date of this proposal. Any returned material may be subject to a restocking fee up to 30%. Any invoice not paid within 30 days will be subject to finance charges of 1.5% monthly/18% annually.

Sign here	Date